



QUOTATION

PRIME WEST BUILDING PTY LTD

ABN:36 645 254 422

16/63 Knutsford Avenue, Rivervale, WA, 6103

DATE: 10/04/2026

QUOTE REFERENCE: Q6104574

VALID UNTIL: 10/05/2026

CONTACT:

Brian : TEL: 0404 816 818

Email: brian@primewestbuilding.com.au

PROJECT:

EconoLodge Motel

85 Great Eastern Highway, Rivervale, WA, 6103

Description

Amount

Econolodge Motel Stage 2

Quotation based on Drawing Project Nos. 2413, Rev 7, dated 23/03/2025;

Internal Ceiling

\$33,262.00

CF1 - Supply and Install suspend ceiling frames and 1 x 13mm Plasterboard lining, flushing and sanding, with R4.0 Ceiling Insulation; (Moisture Resistant PLB to wet areas)

Supply and install GTEK 3 Steps cornice;

B/K within the adjoining ceiling, including the new corridor ceiling and Stage 1 storerooms.

B/K in Level 2 regarding Drawing A10-01, Detail 9.

Internal Wall

\$113,705.00

Z02 - Discontinue Wall

13mm Flush Gyprock lining fixed to 51mm steel stud framing with a discontinuouse gap of 20mm.

MR Plasterboard to wet areas;

Z03 - Resilient Mount F/C Wall

13mm Flush Gyprock lining on Resilient Acoustic mount,with wall insulation;

MR Plasterboard to wet areas;

Non Resilient Mount F/C Wall

13mm Flush Gyprock lining on Non Resilient Acoustic mount, with wall insulation;

MR Plasterboard to wet areas;

Stud Wall

13mm Flush Gyprock lining fixed to 51mm steel stud framing with wall insulation.

MR Plasterboard to wet areas;

TV Wall

13mm Flush Gyprock lining fixed to 51mm steel stud framing with wall insulation.

Applied 16mm Nogging board;

Total Excl. Gst: \$146,967.00

Gst: \$14,696.70

Total Incl. Gst: **\$161,663.70**

Drawing A901 - Main Switchboard Room

Demolish the existing wall and reconstruct it as an FRL 120/120/120 Wall in L1 & L2 - \$9880.00 Excl. Gst.

Doorways to storeroom within the corridor to have Enclosing wall to achieve FRL -/60/60 in GF, L1 & L2 - \$4860.00 Excl. Gst.

Entrance Nib Wall

92mm stud frame with FR Plasterboard to both sides in GF, L1 & L2; - \$8400.00 Excl. Gst.

Access Panel

Supply and install 450x450mm A/P: \$160/Each Excl. Gst.;

Repair and Patching ceiling/wall damaged by others;

(Material + Labor cost - \$85/hour Excl. Gst.)

Thanks for your business!